

Roads and Bridges Development Corporation of Kerala Ltd. (RBDCK)
(A Government of Kerala Undertaking)
2nd floor, Preethi Building, M.V.Road Palarivattom.Kochi 682025
Phone (484)2338205, 2338206, Fax (91-484) 2533294 Website www.rbdck.com
Email: - rbdckltd@gmail.com

QUOTATION NOTICE

Quotation No. RBDCK/T295/Vol I/37

03/12/2019

On behalf of Roads and Bridges Development Corporation of Kerala Limited, its Managing Director invites sealed quotation on item rate basis for Urgent Rectification of Pot Holes and Strip BT (MSS) at Nandi ROB

- | | | |
|-------------------------------------|---|-------------------|
| 1. Period of completion | - | 07 days |
| 2. Date of issue of Schedule | - | 03.12.19 |
| 3. Cost of document | - | Free of cost |
| 4. Last date and time of submission | - | 10.12.19, 3.00 PM |
| 5. Opening | - | 10.12.19, 4.00 PM |

Quotation forms can be obtained from the office of the undersigned and website of RBDCK from 02.12.2019, 4.30 PM to 09.12.2019, 04:30 PM and interested contractors may obtain further details from RBDCK at the address given above in the office hours.

Sd/-

Managing Director

INSTRUCTIONS TO BIDDERS

1. Printed quotation forms can be obtained from the office of the undersigned and website of RBDCK. Quotations submitted not in such printed forms or tenders, incomplete in any respect such as unattested errors and corrections etc will be liable for summary rejection.
2. No quotations received after the specified last date and time will be accepted on any account
3. Details of the work with item wise specifications are given in the subjoined schedule of work. Bidders must quote only a single rate against each item in the Schedule. The rates quoted shall be inclusive ones covering all the operations contemplated in the schedule of works and all incidental works necessary for such operations. The rate quoted shall not be varied on any account whatever and it shall hold good for all items of work done, irrespective of variations of quantity if any
4. Each Bidder should submit along with the tender a signed copy of document in proof of his registration in Kerala PWD as contractor of any class.
5. The acceptance of the quotation rests with the officer inviting tenders who does not undertake to accept the lowest or any particular quotation.
6. The quantities shown in the schedule are only approximate and are subject to variation and if found necessary the contractor is bound to do additional quantities up to 25% above estimate quantities of each item of work at his quoted rate. If any extra items of work not included in the schedule are executed, its rates will be arrived at on the basis of the rules followed in Kerala PWD.
7. Time is the essence of the contract. The work shall be completed within 7 days from the date of receipt of written order to commence the work.
8. Contractor shall appoint qualified engineering representative at site to supervise the work.
9. The rates quoted by the Contractor shall be deemed to be inclusive of the Sales & other taxes including octroi on all materials that the Contractor will have to purchase for performance of this Contract, BUT EXCLUDING GST @ 12% or as decided by the Government from time to time which will be paid in addition to the quoted rates.

SPECIFICATIONS AND SCHEDULE OF WORKS:

Sl. No	Item	Unit	Quantity	Rate	Amount (Rs.)
1	Supplying and stacking 36mm size hard broken stone in standard heaps for measurement.				
		Cum	0.639		
2	Filling up pot holes (cut and formed to regular shapes and all loose and defective materials removed) after supplying a prime coat of hot bitumen using 36mm departmental broken stone and compacting with power roller to get a compact surface.				
		Cum	0.639		
3	Providing and applying tack coat with bitumen emulsion(RS) using emulsion pressure distributor at the rate of 0.20 - 0.30 kg per sqm on the prepared bituminous surface cleaned with mechanical broom.				
		Sqm	77.25		
4	Providing, laying and rolling of close-graded premix surfacing material of 20 mm thickness composed of 11.2 mm to 0.09 mm (Type-A) aggregates using viscosity grade bitumen (VG - 30) to the required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable HMP of appropriate capacity not less than 75 tonnes/hour., laying and rolling with a Smooth wheeled roller 8-10 tonne capacity, and finishing to required level and grade.				
		Sqm	77.25		
	Total				

Dated Signature of Contractor

Name:

Address: