

Roads and Bridges Development Corporation of Kerala Ltd.(RBDCK)
(A Government of Kerala Undertaking)
2nd floor, Preethi Building, M.V.RoadPalarivattom.Kochi 682025
Phone (484)2338205,2338206, Fax (91-484) 2533294 Website www.rbdck.com
Email: - rbdckltd@gmail.com

QUOTATION NOTICE

13/05/2020

On behalf of Roads and Bridges Development Corporation of Kerala Limited, its Managing Director invites sealed quotation on item rate basis for Relaying of Interlocking Tile at Service Road of Palarivattom Flyover

- | | | | |
|-------------------------------------|---|------------|----------|
| 1. Date of issue of Schedule | - | 14/05/2020 | 03:00 PM |
| 2. Last date and time of submission | - | 18/05/2020 | 03:00 PM |
| 3. Opening | - | 18/05/2020 | 04:00 AM |

More details are available at our website and interested contractors may obtain further details from RBDCK at the address given above in the office hours.

Sd/-

Managing Director

INSTRUCTIONS TO BIDDERS

1. Printed quotation forms can be obtained from the office of the undersigned and website of RBDCK. Quotations submitted not in such printed forms, incomplete in any respect such as unattested errors and corrections etc will be liable for summary rejection.
2. No quotations received after the specified last date and time will be accepted on any account
3. Details of the work with specifications are given for each item of work. Bidders must quote only a single rate against each item. The rates quoted shall be inclusive ones covering all the operations contemplated in the schedule of works and all incidental works necessary for such operations. The rate quoted shall not be varied on any account whatever and it shall hold good for all items of work done, irrespective of variations of quantity if any
4. Each Bidder should submit along with the tender a signed copy of document in proof of his registration in Kerala PWD as contractor of any class.
5. The acceptance of the quotation rests with the officer inviting tenders who does not undertake to accept the lowest or any particular quotation.
6. The quantities shown in the schedule are only approximate and are subject to variation and if found necessary the contractor is bound to do additional quantities upto 25% above estimate quantities of each item of work at his quoted rate. If any extra items of work not included in the schedule are executed, its rates will be arrived at on the basis of the rules followed in Kerala PWD.
7. Time is the essence of the contract. The work shall be completed within 7 days from the date of receipt of written order to commence the work.
8. Contractor shall appoint qualified engineering representative at site to supervise the work.
9. The rates quoted by the Contractor shall be deemed to be inclusive of taxes other than GST @ 12% or as decided by the Government from time to time which will be paid in addition to the quoted rates.

Quotation

From

.....

.....

.....

To

The Managing Director,
RBDCK Ltd.
2nd Floor, Preethi Building,
Palarivattom 682025

Sub: Relaying of Interlocking Tile at Service Road of Palarivattom Flyover

Sir,

The rate to relay Interlocking Tile at Service Road of Palarivattom Flyover
In Ernakulam District is quoted below:

Sl.No	Item Description	Unit	Qty	Unit Rate	Amount
1.	Dismantling of cement concrete pavement by mechanical means using pneumatic tools, breaking to pieces not exceeding 0.02 cum in volume and stock piling at designated locations and disposal of dismantled materials up to a lead of 1000 metres, stacking serviceable and unserviceable materials separately	Cum	103.40		
2.	Supplying and stacking 36mm size hard broken stone in standard heaps for measurement.	Cum	22.80		
3.	Man mazdoor engaged for laying, spreading, and compacting stacked 36mm hard broken stone.	No.	2		
4.	Supplying and laying interlocking tile 100 mm or nearest size thickness, minimum strength M 40 including providing a layer of 6 mm aggregate for 5 cm thickness, then laying interlock cobbles in lines and levels as per the directions of the departmental officers at site inclusive of all cost & conveyance charges etc.; complete.	Sqm	93.06		

5	Laying interlocking tile (departmental supply) 100mm or nearest size thickness, minimum strength M40 including providing a layer of 6mm aggregate for 5cm thickness, the laying interlock cobbles in lines and levels as per the directions of the departmental officers at site inclusive of all cost & amp; conveyance charges etc.; complete.	Sqm	10.34		
	Total				

Date and Signature of Contractor

Name:

Address: