

**Roads and Bridges Development Corporation of Kerala Ltd.(RBDCK)**  
(A Government of Kerala Undertaking)  
2<sup>nd</sup> floor, Preethi Building, M.V.RoadPalarivattom.Kochi 682025  
Phone (484)2338205,2338206, Fax (91-484) 2533294 Website [www.rbdck.com](http://www.rbdck.com)  
Email: - [rbdckltd@gmail.com](mailto:rbdckltd@gmail.com)

**QUOTATION NOTICE**

Quotation No.RBDCK/T294/Vol I/21/2020

25/06/2020

On behalf of Roads and Bridges Development Corporation of Kerala Limited, its Managing Director invites sealed quotation on item rate basis for Repair and Maintenance Work of Angadipuram ROB and Parappanagadi ROB at Malappuram District.

- |                                     |   |                     |
|-------------------------------------|---|---------------------|
| 1. Period of completion             | - | 07 days             |
| 2. Date of issue of Schedule        | - | 30/06/2020          |
| 3. Cost of document                 | - | Free of cost        |
| 4. Last date and time of submission | - | 13/07/2020, 3.00 PM |
| 5. Opening                          | - | 13/07/2020, 4.00 PM |

Quotation forms can be obtained from the office of the undersigned and website of RBDCK from 30/06/2020, 10.30 AM to 13/07/2020, 02:30 PM and interested contractors may obtain further details from RBDCK at the address given above in the office hours.

(sd/-)

**Managing Director**

## **INSTRUCTIONS TO BIDDERS**

1. Printed quotation forms can be obtained from the office of the undersigned and website of RBDCK. Quotations submitted not in such printed forms or tenders, incomplete in any respect such as unattested errors and corrections etc will be liable for summary rejection.
2. No quotations received after the specified last date and time will be accepted on any account
3. Details of the work with item wise specifications are given in the subjoined schedule of work. Bidders must quote only a single rate against each item in the Schedule. The rates quoted shall be inclusive ones covering all the operations contemplated in the schedule of works and all incidental works necessary for such operations. The rate quoted shall not be varied on any account whatever and it shall hold good for all items of work done, irrespective of variations of quantity if any
4. Each Bidder should submit along with the tender a signed copy of document in proof of his registration in Kerala PWD as contractor of any class.
5. The acceptance of the quotation rests with the officer inviting tenders who does not undertake to accept the lowest or any particular quotation.
6. The quantities shown in the schedule are only approximate and are subject to variation and if found necessary the contractor is bound to do additional quantities upto 25% above estimate quantities of each item of work at his quoted rate. If any extra items of work not included in the schedule are executed, its rates will be arrived at on the basis of the rules followed in Kerala PWD.
7. Time is the essence of the contract. The work shall be completed within 7 days from the date of receipt of written order to commence the work.
8. Contractor shall appoint qualified engineering representative at site to supervise the work.
9. The rates quoted by the Contractor shall be deemed to be inclusive of the Sales & other taxes including octroi on all materials that the Contractor will have to purchase for performance of this Contract, BUT EXCLUDING GST @ 12% or as decided by the Government from time to time which will be paid in addition to the quoted rates.

**SPECIFICATIONS AND SCHEDULE OF WORKS:**

Sl. No	Item	Unit	Quantity	Rate	Amount (Rs.)
1	Clearing and grubbing road land including uprooting rank vegetation, grass, bushes, shrubs, saplings and trees girth up to 300 mm, removal of stumps of trees cut earlier and disposal of unserviceable materials and stacking of serviceable material to be used or auctioned, up to a lead of 1000 metres including removal and disposal of top organic soil not exceeding 150 mm in thickness. In area of light jungle - By Manual Means				
		Hecter	0.20		
2	Man mazdoor engaged for clearing the drain and other cleaning works				
		Day	7		
3	Applying epoxy mortar over leached, honey combed and spalled concrete surface and exposed steel reinforcement complete as per Technical Specification				
		Sqm	4.80		
4	Providing and applying 2 coats of Anti corrosive paint after cleaning the surface of dirt, dust, oil, grease, efflorescence and applying paint @ of 1 litre for 2 sqm				
		Sqm	2.40		
5	Construction of RCC railing of M30 Grade in-situ with 20 mm nominal size aggregate, true to line and grade, tolerance of vertical RCC post not to exceed 1 in 500, center to centerspacing between vertical post not to exceed 2000 mm, leaving adequate space between vertical post for expansion, complete as per approved drawings and technical specifications				
		RM	8.00		
6	Providing and applying 2 coats of Elastomeric paint to unplastered concrete surface after cleaning the surface of dirt, dust, oil, grease, efflorescence and applying paint @ of 1 litre for 2 sqm				
		Sqm	18.48		
	<b>Total</b>				

Dated Signature of Contractor

Name:

Address: