

Roads and Bridges Development Corporation of Kerala Ltd. (RBDCK)
(A Government of Kerala Undertaking)
2nd floor, Preethi Building, M.V.Road Palarivattom.Kochi 682025
Phone (484)2338205, 2338206, Fax (91-484) 2533294 Website www.rbdck.com
Email: - rbdckltd@gmail.com

QUOTATION NOTICE

Quotation No. RBDCK/T294/Vol I/ 36/2020

30/07/2020

On behalf of Roads and Bridges Development Corporation of Kerala Limited, its Managing Director invites sealed quotation on item rate basis for Repair and Maintenance Works of Bekkal ROB and Cheruvathur ROB in Kasargode District

- | | | |
|-------------------------------------|---|---------------------|
| 1. Period of completion | - | 15 days |
| 2. Date of issue of Schedule | - | 03/08/2020 |
| 3. Cost of document | - | Free of cost |
| 4. Last date and time of submission | - | 17/08/2020, 3.00 PM |
| 5. Opening | - | 17/08/2020, 4.00 PM |

Quotation forms can be obtained from the office of the undersigned and website of RBDCK from 03/08/2020, 10.30 AM to 17/08/2020, 02:30 PM and interested contractors may obtain further details from RBDCK at the address given above in the office hours.

Sd/-

Managing Director

INSTRUCTIONS TO BIDDERS

1. Printed quotation forms can be obtained from the office of the undersigned and website of RBDCK. Quotations submitted not in such printed forms or tenders, incomplete in any respect such as unattested errors and corrections etc will be liable for summary rejection.
2. No quotations received after the specified last date and time will be accepted on any account
3. Details of the work with item wise specifications are given in the subjoined schedule of work. Bidders must quote only a single rate against each item in the Schedule. The rates quoted shall be inclusive ones covering all the operations contemplated in the schedule of works and all incidental works necessary for such operations. The rate quoted shall not be varied on any account whatever and it shall hold good for all items of work done, irrespective of variations of quantity if any
4. Each Bidder should submit along with the tender a signed copy of document in proof of his registration in Kerala PWD as contractor of any class.
5. The acceptance of the quotation rests with the officer inviting tenders who does not undertake to accept the lowest or any particular quotation.
6. The quantities shown in the schedule are only approximate and are subject to variation and if found necessary the contractor is bound to do additional quantities up to 25% above estimate quantities of each item of work at his quoted rate. If any extra items of work not included in the schedule are executed, its rates will be arrived at on the basis of the rules followed in Kerala PWD.
7. Time is the essence of the contract. The work shall be completed within 15 days from the date of receipt of written order to commence the work.
8. Contractor shall appoint qualified engineering representative at site to supervise the work.
9. The rates quoted by the Contractor shall be deemed to be inclusive of the Sales & other taxes including control on all materials that the Contractor will have to purchase for performance of this Contract, BUT EXCLUDING GST @ 12% or as decided by the Government from time to time which will be paid in addition to the quoted rates.

SPECIFICATIONS AND SCHEDULE OF WORKS:

Sl. No	Item	Unit	Quantity	Rate	Amount (Rs.)
1	Construction of RCC railing of M30 Grade in-situ with 20 mm nominal size aggregate, true to line and grade, tolerance of vertical RCC post not to exceed 1 in 500, center to center spacing between vertical post not to exceed 2000 mm, leaving adequate space between vertical post for expansion, complete as per approved drawings and technical specifications.				
		RM	8.00		
2	Providing and applying 2 coats of Elastomeric paint to unplastered concrete surface after cleaning the surface of dirt, dust, oil, grease, efflorescence and applying paint @ of 1 litre for 2 sqm.				
		Sqm	5.68		
3	Furnishing and Placing Reinforced Cement Concrete Grade M20 Using Concrete Mixer as per drawing and Technical Specification. For Footpath slab				
		Cum	2.40		
4	Supplying, fitting and placing HYSD bar reinforcement in super-structure complete as per drawing and technical specifications-For Footpath slab				
		MT	0.192		
5	Providing and fixing of retro-reflectorized cautionary, mandatory and informatory sign with 7years warranty manufactured as per IRC :67 made of Type IV micro prismatic grade sheeting vide clause 801.3.3 fixed over aluminium sheeting, 2 mm thick/ aluminium composite material sheeting 4 mm thick with suitable back supporting frame of MS angle 25x25x3 and supported on GI pipe pole 50mm NB conforming to IS 1239 firmly				

	fixed to the ground by means of properly designed foundation with M 15 grade cement concrete min size 45 cm x 45cm x 60 cm, 60 cm below ground level including painting all exposed surface with 2 coats of epoxy painting over epoxy primer and as per approved drawing and clause 801 including lettering symbols etc. 60 cm x 45 cm rectangular.				
		Each	2.00		
6	Clearing and grubbing road land including uprooting rank vegetation, grass, bushes, shrubs, saplings and trees girth up to 300 mm, removal of stumps of trees cut earlier and disposal of unserviceable materials and stacking of serviceable material to be used or auctioned, up to a lead of 1000 meters including removal and disposal of top organic soil not exceeding 150 mm in thickness In area of light jungle – By Manual Means				
		Hecter	0.06		
	Total				

Dated Signature of Contractor

Name:

Address: