

**Roads and Bridges Development Corporation of Kerala Ltd.(RBDCK)**  
(A Government of Kerala Undertaking)  
2<sup>nd</sup> floor, Preethi Building, M.V.RoadPalarivattom.Kochi 682025  
Phone (484)2338205,2338206, Fax (91-484) 2533294 Website [www.rbdck.com](http://www.rbdck.com)  
Email: - [rbdckltd@gmail.com](mailto:rbdckltd@gmail.com)

**QUOTATION NOTICE**

Quotation No. RBDCK/ T294/ Vol I/ 34/ 2020

30/07/2020

On behalf of Roads and Bridges Development Corporation of Kerala Limited, its Managing Director invites sealed quotation on item rate basis for Repair and Maintenance Work of Kadukkamkundu ROB, Victoria College ROB and Sulthanpet ROB in Palakkad District

- |                                     |   |                     |
|-------------------------------------|---|---------------------|
| 1. Period of completion             | - | 15 days             |
| 2. Date of issue of Schedule        | - | 03/08/2020          |
| 3. Cost of document                 | - | Free of cost        |
| 4. Last date and time of submission | - | 17/08/2020, 3.00 PM |
| 5. Opening                          | - | 17/08/2020, 4.00 PM |

Quotation forms can be obtained from the office of the undersigned and website of RBDCK from 03/08/2020, 10.30 AM to 17/08/2020, 02:30 PM and interested contractors may obtain further details from RBDCK at the address given above in the office hours.

**Sd/-**

**Managing Director**

## **INSTRUCTIONS TO BIDDERS**

1. Printed quotation forms can be obtained from the office of the undersigned and website of RBDCK. Quotations submitted not in such printed forms or tenders, incomplete in any respect such as unattested errors and corrections etc will be liable for summary rejection.
2. No quotations received after the specified last date and time will be accepted on any account
3. Details of the work with item wise specifications are given in the subjoined schedule of work. Bidders must quote only a single rate against each item in the Schedule. The rates quoted shall be inclusive ones covering all the operations contemplated in the schedule of works and all incidental works necessary for such operations. The rate quoted shall not be varied on any account whatever and it shall hold good for all items of work done, irrespective of variations of quantity if any
4. Each Bidder should submit along with the tender a signed copy of document in proof of his registration in Kerala PWD as contractor of any class.
5. The acceptance of the quotation rests with the officer inviting tenders who does not undertake to accept the lowest or any particular quotation.
6. The quantities shown in the schedule are only approximate and are subject to variation and if found necessary the contractor is bound to do additional quantities upto 25% above estimate quantities of each item of work at his quoted rate. If any extra items of work not included in the schedule are executed, its rates will be arrived at on the basis of the rules followed in Kerala PWD.
7. Time is the essence of the contract. The work shall be completed within 15 days from the date of receipt of written order to commence the work.
8. Contractor shall appoint qualified engineering representative at site to supervise the work.
9. The rates quoted by the Contractor shall be deemed to be inclusive of the Sales & other taxes including control on all materials that the Contractor will have to purchase for performance of this Contract, BUT EXCLUDING GST @ 12% or as decided by the Government from time to time which will be paid in addition to the quoted rates.

**SPECIFICATIONS AND SCHEDULE OF WORKS:**

<b>Sl. No</b>	<b>Item</b>	<b>Unit</b>	<b>Quantity</b>	<b>Rate</b>	<b>Amount (Rs.)</b>
1	Clearing and grubbing road land including uprooting rank vegetation, grass, bushes, shrubs, saplings and trees girth up to 300 mm, removal of stumps of trees cut earlier and disposal of unserviceable materials and stacking of serviceable material to be used or auctioned, up to a lead of 1000 metres including removal and disposal of top organic soil not exceeding 150 mm in thickness. In area of light jungle - By Manual Means				
		Hecter	0.26		
2	Man mazdoor engaged for clearing the choked drain and other cleaning works				
		Day	8		
3	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead of 1000 metres. Cement Concrete Grade M-15 & M-20 - By Mechanical Means				
		Cum	9.83		
4	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead of 1000 metres - Cement Concrete Grade M-15 & M-20. - By Manual Means				
		Cum	6.55		
5	Dismantling of flexible pavements and disposal of dismantled materials up to a lead of 1000 metres, stacking serviceable and unserviceable materials separately Bituminous course - By Mechanical Means				
		Cum	0.99		
6	Supplying and laying interlocking tile 100 mm or nearest size thickness, minimum strength M 40 including providing a layer				

	of 6 mm aggregate for 5 cm thickness, then laying interlock cobbles in lines and levels as per the directions of the departmental officers at site inclusive of all cost & conveyance charges etc.; complete				
		Sqm	25.50		
7	Providing, laying and rolling of close-graded premix surfacing material of 20 mm thickness composed of 11.2 mm to 0.09 mm (Type-A) aggregates using viscosity grade bitumen ( VG - 30) to the required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable HMP of appropriate capacity not less than 75 tonnes/hour., laying and rolling with a Smooth wheeled roller 8-10 tonne capacity, and Finishing to required level and grade.				
		Sqm	885.00		
8	Providing and applying tack coat with bitumen emulsion (RS) using emulsion pressure distributor at the rate of 0.20 - 0.30 kg per sqm on the prepared bituminous surface cleaned with mechanical broom.				
		Sqm	885.00		
9	Plain/Reinforced Cement Concrete in Open Foundation complete as per Drawing and Technical Specifications PCC Grade M20 (Without formwork)				
		cum	0.675		
	<b>Total</b>				

Dated Signature of Contractor

Name:

Address: